
Fiche technique / Datasheet

Numéro d'article / Article number: 3B211K

Numéro EAN / EAN number: 4250384715861
Catégorie de fret / Freight category: D

Palette combinée pour 30 clôtures de chantier et 31 pieds de clôture de chantier, Palette combi

Combi pallet for 30 construction fences and 31 construction fence feet, Combi pallet



Description de l’article

Palette combinée pour 30 clôtures de chantier et 31 pieds de clôture de chantier

Palette combinée , , 30x clôtures de chantier et 31x pieds de clôtures de chantier, 2 côtés carrossables , Tubes verticaux et traverses en profilé C coudé de 160 x 75 mm, Dimensions: 3,56 x 1,14 m, Exécution: galvanisée

- Palette combi

Item description

Combi pallet for 30 construction fences and 31 construction fence feet

Combi pallet

·for 30x construction fences and 31x construction fence feet
·2-sided trafficable
·uprights and crossbars made of 160 x 75 mm C-profile
·dimensions: 3,56 x 1,14 m
·Finish: galvanised

- Combi pallet

Données techniques

Poids: 185 kg
Dimensions: 1140 mm x 3530 mm x 80 mm
matériau:
S235 JR

surface:
galvanisé à chaud suivant DIN ISO 1461

Technical specifications

Weight: 185 kg
Dimensions: 1140 mm x 3530 mm x 80 mm
material:
S235 JR

surface:
hot dipped galvanized acc. to DIN ISO 1461

* Toutes les données sont des valeurs indicatives (en partie avec les arrondis habituels dans la branche pour une meilleure compréhension) et servent uniquement à la compréhension du produit, mais pas comme base pour la construction d'accessoires, de supports de stockage, d'adaptations, de produits combinés ou autres. Toutes les indications sont fournies sans garantie, nous déclinons toute responsabilité pour d'éventuelles erreurs et les conséquences qui en résultent.
* All data are approximate values (partly with industry-standard rounding for better understanding) and serve only for product understanding, but not as a basis for the design of accessories, storage solutions, adaptations, combination products or the like. All information is without guarantee, for possible errors and resulting consequences we assume no responsibility.